



AGENDA ITEM EXECUTIVE SUMMARY

Agenda Item:	Approve purchase of Two 2021 Peterbilt Model 348 single axle dump and snowplow from JX truck Centers of Elmhurst		
Presenter & Title:	Nate Landers, Superintendent of Streets, Fleets, and Facilities		
Date:	April 5, 2021		
Please Check Appropriate Box:			
<input checked="" type="checkbox"/>	Committee of the Whole Meeting	<input type="checkbox"/>	Special Committee of the Whole Meeting
<input checked="" type="checkbox"/>	City Council Meeting	<input type="checkbox"/>	Special City Council Meeting
<input type="checkbox"/>	Public Hearing	<input type="checkbox"/>	Other -
Associated Strategic Plan Goal/Objective:EMS-II			
Estimated Cost: \$430,464		Budgeted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Other Funding? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
If "Other Funding," please explain how the item will be funded:			
Executive Summary:			
<p>The Fiscal Year 2022 budget has funds allocated to replace a 1998 GMC (G-3420) and 2002 GMC (G-3043) single axle snowplows due to their years in service and the number of repairs made to the vehicles on an annual basis. The computer on 3420 has gone bad and the truck no longer runs. This truck is the primary anti-icing vehicle and parts to repair this truck are no longer available. 3043 is running into the same issues. While the truck still runs, due to the age of the vehicle parts are becoming harder and harder to locate. The new trucks will come with a plow, wing plow, salt spreader, anti-icing unit and pre-wet capabilities. Payment will be made during fiscal year 2022 after delivery of the trucks to Public Works. Due to the availability of cabs and chassis and the minimum 6-month build time, staff is seeking approval to order these vehicles prior to the start of budget year 2022. Staff is utilizing the cooperative purchasing agreement with Sourcewell for the purchase of the truck. The cost to purchase both trucks is \$430,464.00</p>			
Attachments: <i>(please list)</i>			
<ul style="list-style-type: none"> • Resolution • Specifications and quote 			
Voting Requirements:			
<p><i>This motion requires 6 affirmative votes for passage.</i></p> <p><i>The Mayor may vote on three occasions: (a) when the vote of the aldermen or trustees has resulted in a tie; (b) when one half of the aldermen or trustees elected have voted in favor of an ordinance, resolution, or motion even though there is no tie votes; or (c) when a vote greater than a majority of the corporate authorities is required by state statute or local ordinance to adopt an ordinance, resolution, or motion.</i></p>			
Recommendation / Suggested Action: <i>(how item should be listed on agenda)</i>			
<p>Recommend approval of a Resolution Authorizing the City Administrator to purchase two 2021 Peterbilt Model 348 single axle dump trucks with plows, spreaders, and anti-icing systems in the amount not to exceed \$430,460 from JX Truck Centers of Elmhurst through Sourcewell.</p>			

RESOLUTION NO. 2021-4:

**RESOLUTION AUTHORIZING THE PURCHASE
OF TWO SINGLE AXLE DUMPS AND SNOWPLOWS**

BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF GENEVA, KANE COUNTY, ILLINOIS, as follows:

SECTION 1: That the City Administrator is authorized to purchase, on behalf of the City of Geneva, two 2021 Peterbilt model 348 single axle dumps and snowplows from JX Truck Centers through the Sourcewell Cooperative Purchasing Program at a price not to exceed \$430,464.00

SECTION 2: This Resolution shall become effective from and after its passage as in accordance with law.

PASSED by the City Council of the City of Geneva, Kane County, Illinois, this 19th day of April, 2019

AYES: __ NAYS: __ ABSENT: __ ABSTAINING: __ HOLDING OFFICE: __

Approved by me this 19th day of April, 2021.

Mayor

ATTEST

City Clerk



January 15, 2021

Joe Czysczon

Dear Joe,
JX Peterbilt – Wadsworth is pleased to present a price quotation for 2 New 2022 Peterbilt Model 348 single axle chassis with the enclosed specification.

2021 Sourcewell Contract #060920-PMC

List Price 2021 spring build	\$139,399.00
Peterbilt Model 348 Sourcewell 2021 new discount 35% off list	-(48,789.00)

Price for chassis only with Sourcewell discount	\$90,609.00
Additional JX good customer discount -(1,000.00)	cost \$89,690.00 each

Sourced Goods and services

Body install supply and install by others	xxxxxxx
Fuel, Def and Detail,title doc fee and plates/title	\$778.00

Total cost goods and services	\$778.00
-------------------------------	-----------------

Final Sourcewell chassis price each cost with Goods and services included
\$90,468.00

2 units \$90,468.00 each Total \$180,936.00

Order Requirements: Signed final set of truck specifications, Signed JX purchase order contract. And Village Purchase Order.

Sincerely,

Richard Venuso

Rick Venuso
Sales Executive.
Cell 224 678 6669
JX Peterbilt – Wadsworth

PO Box 189, Wadsworth IL 60083
42400 Old Hwy 41
Business 847.395.7222 Toll Free 800.243.0524 Fax 847.395.7240

Visit us at
www.JXE.com



HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 1
Quote #134907
Rev #106

To: CITY OF GENEVA, IL
Attn: JOE CZYSCZON
Quote Date: 1/15/2021
Valid Until: 2/14/2021
Sourcewell Contract# 080818-HPI
Sourcewell #: Sourcewell
Quoted:

Quoted By: Rob Florio
Phone: 847-836-4996
Cell: 847-257-2452
Fax: 563-927-7108
Email: rflorio@hendersonproducts.com

Henderson Products is pleased to present the following quote. Please contact us if you have any questions.

MARKE SA Dump Body

BODY LENGTH: **10ft BODY LENGTH**
SIDE STYLE: **STRAIGHT SIDES**
SIDE HEIGHT (FROM FLOOR): **30" SIDE HEIGHT**
REAR BODY PROFILE: **STANDARD STRAIGHT VERTICAL GATE**
REAR CORNER POSTS: **REAR BOLSTERS 8" ABOVE SIDES**
BOARD POCKETS: **2" WIDE BOARD POCKETS**
HOIST TYPE: **TRN MOUNT TELE HOIST W/ SUBFRM, INTERNAL DOGHOUSE**
HOIST CYLINDER/MODEL: **MAILHOT CS-SERIES, DOUBLE ACTING, CS90-4.5-3DA**
HYDRAULIC PUMP: **NO FACTORY SUPPLIED HYDRAULIC PUMP**
CYLINDER CRADLE STYLE: **STANDARD HOIST CRADLE**
INSTALL SUBFRAME AND/OR CYLINDER: **SHIP LOOSE - DEALER TO INSTALL**
EXTRA BODY PROP: **NO EXTRA BODY PROP**
HYDRAULIC RESERVOIR: **NO RESERVOIR - DEALER TO SUPPLY**
FLOOR MATERIAL: **1/4" AR400 FLOOR**
FLOOR TO SIDE RADIUS: **5" RADIUS FLOOR TO SIDE**
LONGSILL MATERIAL: **5" I-BEAM LONGSILLS (STANDARD SKIP WELD)**
SIDES/HEADSHEET MATERIAL: **10GA 201SS SIDES/HEAD**
SIDE BRACING TYPE: **DOUBLE V-CRIMP INTERMEDIATE SIDE BRACES**
SIDE BRACE MATERIAL: **DOUBLE V-CRIMP SIDE BRACE**
TOP RAIL STYLE: **FLAT (2" FLAT, THEN SLOPED)**
CONTOURED FRONT CORNER POSTS: **NO FRONT CORNER POSTS**
REAR CORNER POST MATERIAL: **7GA 201SS REAR CORNER POSTS**
TAILGATE STYLE: **STANDARD TAILGATE**
TAILGATE SHEET MATERIAL: **10GA 201SS TAILGATE SHEET**
TAILGATE BRACING: **SINGLE HORIZONTAL TAILGATE BRACE**
TAILGATE BRACE MATERIAL: **10GA 201SS TAILGATE BRACING**
TAILGATE TOP PIVOT HARDWARE: **1-1/4" PINS, 1" PLATES, NON-GREASABLE**
TAILGATE LATCH TYPE: **DBL ACTING AIR CYL TG RELEASE, GREASABLE SS BUSHINGS**
TAILGATE RELEASE VALVE: **NO TAILGATE RELEASE VALVE**
TAILGATE PIN LANYARDS: **NO TAILGATE PIVOT PIN LANYARDS**
TAILGATE LIFT LOOP: **NO TAILGATE LIFT LOOP OR DRING**
LATCH JAWS: **LOWER TG LATCH JAWS, GREASABLE**
COAL CHUTE: **COAL CHUTE**
COAL CHUTE TYPE: **STD 13.5" COAL CHUTE (201SS)**
COAL CHUTE QUANTITY: **SINGLE COAL CHUTE**
COAL CHUTE INSTALLED: **COAL CHUTE INSTALLED**





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE #6

Page 2
Quote #134907
Rev #106

COAL CHUTE LOCATION: **CENTER**
REAR FACE LIGHT HOLES: **(2) OBOURND LIGHT HOLES, EA BOLSTER REAR FACE**
REAR SIDE MARKER LIGHT HOLE: **STD 2.5" SIDE MARKER LIGHT HOLES**
EXTERIOR LIGHT BOXES INSTALLED: **NO EXTERIOR LIGHT BOXES**
LIGHTING PACKAGE: **NO OEM LIGHTING PACKAGE**
BODY HINGE CONSTRUCTION: **STD SUBFRAME INTEGRAL HINGE**
BODY HINGE TYPE: **GREASELESS COMPOSITE BUSHING HINGE BLOCKS (I)**
BODY HINGE PAINT: **YES, REAR HINGE PAINTED @ FACTORY**
PAINT PREPARATION: **SS WASH-NATURAL FINISH, PRIME MILD PARTS (201/304SS BODY)**
CABSHIELD STYLE: **NO CABSHIELD**
ASPHALT LIP: **WELD ON ASPHALT LIP**
ASPHALT LIP MATERIAL: **201 STAINLESS STEEL**
ASPHALT LIP STYLE: **12" WELD ON, 7GA 201SS WITH 1/4" ENDPLATES**
ASPHALT LIP INSTALLED: **ASPHALT LIP SHIPPED LOOSE**
WALK RAILS: **NO WALKRAILS ON LOWER RUBRAILS**
TARP RAILS: **NO TARP RAILS**
SIDE LADDERS: **(YES) SIDE LADDER - Pick From List Below**
SIDE LADDER MATERIAL: **STAINLESS STEEL LADDER CONSTRUCTION - Pick From List Below**
DRIVER'S SIDE FRONT LADDER: **3 STEP PULL OUT LADDER (201SS)**
INSTALL DRIVER SIDE FRONT LADDER: **YES, INSTALL DRIVERS SIDE FRONT LADDER**
DRIVER'S SIDE REAR LADDER: **NO DRIVERS SIDE REAR LADDER**
CURBSIDE FRONT LADDER: **NO CURBSIDE FRONT LADDER**
CURBSIDE REAR LADDER: **NO CURB SIDE REAR LADDER**
STEP(S): **NO STEP(S)**
GRAB HANDLES: **GRAB HANDLE, DRIVERS SIDE FRONT**
SIDEBOARDS: **NO SLOPED SIDEBOARDS**
Show Options: **Show Options**
RUBBER MOUNTING PADS: **NO RUBBER MOUNTING PADS**
VIBRATOR MOUNTING PAD: **VIBRATOR MOUNTING PAD, BETWEEN LONGSILLS (MILD)**
REAR APRON FILLER PLATE (FOR TGS SANDER): **NO REAR APRON FILL PLATE**
INSTALL TGS SPREADER: **NO TGS INSTALL**
HEATED BODY: **NO HEATED BODY OPTION**
CRADLE MOUNT TOOLBOX: **NO TRIANGULAR CRDL MOUNT TOOLBOX (SLOPED HEAD P2P ONLY)**
TOOLBOX (BODY INTEGRAL): **NO INTEGRAL BODY TOOLBOX**
Option 1 Description: **140627.201 Cab Shield**
Option 2 Description: **PIn on style asphalt lip**

TGS salt / sand spreader

TROUGH MATERIAL: **201SS**
AUGER SIZE AND TYPE: **6" dia. auger, direct drive**
MOUNTING BRACKETS: **Std brackets for 96" wide bodies**
MOTOR W/ SPEED SENSOR: **Motor w/integral speed sensor**
Option 1 Description: **Slurry Tube**

PWS liquid pre-wetting system





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 3
Quote #134907
Rev #106

Power Source: **Hydraulic Powered Pump**
Application: **Munibody**
Product Size: **Munibody 9ft RDO**
Control Box: **No Valve, Hydraulic Powered Pump and Flow Meter**
Pump: **Upgraded Pump Rated at 8.2 GPM**
Console: **None-Deduct PWSH-I Console**
Tank Size: **No Tank(s)-Deduct MUNI 75 gal tank**
Spray Assembly: **No Nozzles**
Mounting Hardware: **No Mounting Hardware or N/A**

Reversible snow plow

Plow Length: **12' length**
Moldboard Trip: **Full trip with 2 external compression springs**
Pushframe Type: **Full Width Push Frame with top mount cylinders, Std. Angle**
Moldboard Height: **36" height**
Moldboard Shield: **Integral shield**
Moldboard Sheet Material: **10 GA GR50 steel (standard)**
Hydraulic Cylinders: **4" x 2" x 10" reversing nitrided cylinders**
Paint: **Henderson Orange**
Running Gear Type: **Skid Shoes**
Skid Shoes, Pair Installed: **1" x 6" carbide rect. skid shoes w/ screw jack adjustment**
12" Rubber Deflector: **Yes, w/ SS Backer**
Install Rubber Deflector: **Yes**
36" Plastic Side Markers, Pair: **Yes**
Parking Jack, Screw Adjustable: **Yes**
Install Parking Jack: **Yes**
Cutting Edge: **3/4" x 6" Carbide cutting edge with cover blade**
Moldboard Shoes, Pair Installed: **Yes**
Hitch, Plow Portion: **Quick Link hitch**
Plow Portion Installed on Plow: **Yes**
Hitch, Truck Portion: **See HPH or HCH for Truck portion hitch**
Custom Option Fields: **Note Custom Details Below**
Option 1 Description: **140590 Pete Hitch**
Option 2 Description: **163899 Curb Guard Carbide RH, Winter equipment-Installed**
Option 3 Description: **163900 Curb Guard Carbide LH, Winter equipment- Installed**
Option 4 Description:
Option 5 Description:
Option 6 Description:

Snow Plow Hitch

Hitch, Truck Portion: **Quick Link hitch, Low Profile**
Lift Arm Type: **Fold down arm for safe storage-current single point lift**
Lift Arm Size: **Telescoping Arm with 4x4x3/8" outer and 3x3x3/4" inner tube**
Lift Lug(s): **Standard 1/2" plate with key holes for 1/2" chain**





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 4
Quote #134907
Rev #106

Hydraulic Lift Cylinder: 4" x 2" x 10" Double Acting Nitrided Lift Cylinder

Custom Options: **Note Custom Details Below**

Option 1 Description:

Option 2 Description:

Option 3 Description:

Henderson Wing System

WING CONFIGURATION TYPE: **LIGHT DUTY**

WING SYSTEM: **REAR OF CAB SYSTEM**

REAR BRACE LOCATION: **REAR BRACE AHEAD OF REAR AXLES**

WING SIDE LOCATION: **RIGHT HAND SIDE**

TRIP TYPE: **ADJUSTABLE TRIP EDGE MOLDBOARD**

WING BRACES: **1 SHOCK BRACE**

CUTTING EDGE LENGTH: **8' CUTTING EDGE**

CUTTING EDGE MATERIAL: **3/4 X 6 CARBIDE CUTTING EDGE**

MOLDBOARD MATERIAL: **10GA GR50 CURVED MOLDBOARD**

MOLDBOARD HEIGHT AND SHAPE: **32" STRAIGHT MOLDBOARD**

MOLDBOARD DISCHARGE: **6" FLARE ON DISCHARGE W/BEAD**

MOLDBOARD BOTTOM ANGLE: **4 X 4 X .50 BOTTOM ANGLE**

MOLDBOARD TOP FLANGE: **MOLDBOARD BOXED-IN TOP FLANGE**

MOLDBOARD ADD ONS: **MOLDBOARD CENTER LIFT EYE**

FRONT MAST TYPE: **8" LIFT/11" CYL HYD FRONT MAST**

FRONT MAST MOUNT: **FRONT CROSSTUBE & CHEEKPLATES**

REAR SUPPORT AND MAST: **CHEEKPLATES W/REAR CROSS TUBE**

MOLDBOARD HEEL LIFT: **FRONT MLDBRD HEEL LIFT, 3" CYL**

PAINT: **MB STD ORANGE, ALL ELSE BLACK**

ORANGE SIGHT MARKER, SHIP LOOSE: **ORANGE SIGHT MARKER, SHIP LOOSE**

HEEL LIFT HOLDING VALVE: **HEEL LIFT HOLDING VALVE**

Option 1 Description: **163900 Curb Guard Carbide, Winter Equipment- Installed**

Option 2 Description: **159804 Carbide moldboard Shoe, Winter Equipment-Installed**

Installation Workup

Facility: **IDC-IL**

Chassis Delivery To Henderson: **Truck Dealer/Customer Delivers**

Completed Truck Delivery Method: **Henderson Delivers (100 miles or less)**

Chassis Make: **Peterbilt**

Chassis Model Yr: **2021**

Chassis Model: **348**

Front Axle Rating: **20000**

Rear Axle Rating: **40000**

Front Frame Ext?: **Yes**

Frnt Frame Ext Type: **Partial**

Front Frame Wall: **Single Wall**

Front Frame Width: **34"**

Pump Location: **Transmission Mount Pump**





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 5
Quote #134907
Rev #106

Transmission Type: **Automatic**
Transmission Model: **Allison Transmission**

Hitch Type: **Low Profile or Manual Tilt Type Hitch**
Mount Type: **Engineered Truck Hitch (sales to order hitch w/ unit)**
Mount Spec: **140590 Peterbuilt 348 Specific Hitch Supplied with Equip**
Front Bumper: **OEM Bumper Cut and Split**

Front Plow Type: **Standard Henderson Plow**
Plow Markers (Front Plow): **IDC Install of fact supplied markers, sales to order w/ unit**

Rubber Deflector Install: **Supplied/Installed @ Factory, sales to order w/ unit**
Running Gear Install: **Supplied/Installed @ Factory (sales to order w/ unit)**
Moldboard Shoes Install: **Supplied/Installed @ Factory (sales to order w/ unit)**
Front Plow Curb Guards: **Supplied/Installed @ Factory (Sales to order with unit)**
Plow Jack Install: **Supl'd/Instl'd on plow @ Factory, Sales order with unit**

Wing Type: **Install Mid-Mount Wing System (Non-extend)**
Wing Stop: **Yes (factory supplied)**
Plow Markers (Wing Plow): **IDC Install fact supl'd marker, single, sales order w unit**
Mldbrd Shoe(s) Install (Wing): **Supplied/Installed @ Factory (sales to order w/ unit)**
Curb Guard (Wing Plow): **Supplied/Installed @ Factory (Sales to order with unit)**
Wing Options 1: **Add Reflective Tape to Wing 136402 (20)**

Dump Body Type: **Mark E Single Axle**
Floor Length: **(10') Floor length**
Hoist Type: **Tele Trun HoIst with Subframe, Internal Doghouse**
Cylinder Type: **Double Acting**
Body Material (Sides/ends): **Stainless Steel Type Body Material**
Tailgate Release Type: **IDC supplied Electric over air valve**
Pressure Protection Valve: **Direct to air tank valve (All chassis except Int & Mack)**

Cabshield Install: **Supl'd by fact, welded to body @ IDC, sales to order w/ unit**
Asphalt Lip (FF Only): **Supl By Fact, Inst @ IDC, Pin on (Sales order with unit)**
Ladder(s): **Supplied/Installed @ Factory (sales to order w/ unit)**
Shovel Holder: **(1) IDC Supl'd Spring Loaded SS Shovel Holder w/ SS brckt**
Shovel Holder Loc (1): **Driver side body**
Vibrator: **Buyers Vib, 2500 lb (SA) (order vib pad on unit)**
Sideboards: **Wood (Un-Painted), supplied/installed by IDC**
Sideboard Spec: **162233x2**

Sideboard Notes:
2"x10"x10' side boards

Body Spec Notes:





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 6
Quote #134907
Rev #106

Spreader Type: **TGS**
TGS Drive Type: **Hydraulic Drive**
TGS Spinner Configuration: **Single Spinner Install**
TGS Body Type: **Standard straight gate body install**
TGS mounting type: **Pin on style (interchangeable with asph lip, if applicable)**
HYD QD Mount Brackets: **Stainless Steel QD Mount in front of dump body bolster**

Prewet/Liquid System: **Frame Mount Prewet System**
Configuration: **IDC Supplied (sales to quote from vendor)**
Vendor Supplied Kit: **Dual 120 gal BTC prewet tanks pn: 118175**
Install Location: **Cradle Mount (verify fit or CA/CT if Req'd)**
Drive Configuration: **Hydraulic Drive, Henderson Supplied (Sales to order w/unit)**
Controls: **Supplied by IDC (sales to order w/ hyd cntrls)**
Feedback Sensor: **Yes (Sales to order w/unit)**
Slurry Tube: **Factory Supplied/Installed (sales to order w/unit)**
Liquid Options 1: **Flush Tank 161566 (1) 165484.201 (1)**

Liquid Details:

Chassis Accessories: **Yes (SELECT RELATED OPTIONS BELOW)**
Mudflaps (Rear): **Swinging w/Logo**
Mudflap Type (Rear): **36" Swinging, SS (with LOGO)**
Mudflaps (Front): **Body Mounted Stone Shields**
Mudflap Type (Front): **Body Mounted, SS Stone Shields (welded to body) (no MK3/mb3)**
Pintle Plate: **Yes (select from options below)**
Pintle Plate Configuration: **3/4" Plate, PH20 Holes, SA w/ SubFrm (3LTC)**
Pintle Plate D-Rings: **Qty (2) 3/4" D-rings**
Pintle Hook: **20 Ton**
Trailer Plug (1): **6 Pin Trailer Plug, Truck End**
Truck Wash: **Complete Truck Wash/Clean/Vac 1**
Warranty: **Standard 1 Year Warranty**
Reflective Tape: **Reflective Tape, Henderson Logo (60' Linear)**
Install Touch-up: **Basic Installation Touch-Up**

Electrical: **Yes (SELECT RELATED OPTIONS BELOW)**
Power Distribution Panel: **Power Distribution Panel**
Misc Electrical Supplies: **Req'd Misc Elect Supplies**
Plow Lights: **Plow Lts, ABL, Heated**
Plow Light Brackets: **Plow Lt Brckts, SS, PETERBILT 348, Pair**
Worklight(s) QTY: **(QTY 4) Work Lights (Select type below)**
Worklight (1) Type: **LED, Worklight, 4in Round (Optilux)**
Worklight (1) Gen Location: **Tailgate Spinner**
Worklight (2) Type: **LED, Worklight, 4in Round (Optilux)**
Worklight (2) Gen Location: **Tailgate Spinner**
Worklight (3) Type: **LED, Worklight, 4in Round (Optilux)**
Worklight (3) Gen Location: **Front Steps**
Worklight (4) Type: **LED Amber Wing Lts, vis w/wing up/dwn, 2 Lts, non-extble wing**





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 7
Quote #134907
Rev #106

Worklight (4) Gen Location: **Rear of Wing**
Rear Dump Bolster (S/T/T): **LED S/T/T, kit (West) (order holes)**
Rear Dump Bolster (Back-up): **B/U Lights, LED, Clear, Oval, pair (Order holes with body)**
Back up alarm: **Backup Alarm, 97db**
Junction Box/Backup Alarm Bracket: **Backup Alarm Bracket Installed**
Body up switch/light: **Body UP Switch/Body Up Light (Trucklite)**
Brake controller: **Brake Controller, Voyager Brake Controller**
License Plate Lights: **IDC Supplied License Plate Light Gray Housing**
Backbone & Wire Standoffs: **10' Backbone (For SA)**
Camera: **MS Foster**
Camera Kit: **Camera Sys, 7" Monitor, 2 Cameras w/wash & Exten Cble**
IDC Light Package: **72" Justice (ILDOT) w/2 wk lites, Short Risers**
Pavement Temp Sensor: **Roadwatch kit w/ stand alone display**
Electrical Install Opt 1: **Peterbilt electrical kit**

Electrical Spec Notes:

Hydraulics: **Full Hydraulic Package**
Hyd Supplier: **Certified (Select Pkg Below)**
Hyd Supplier (Spec): **Certified 11018928**
Controls Type: **Cable Controls**
Cable Qty: **6 Functions**
PTO Type: **Included in Hydraulics Package**
Reservoir Type: **Supplied With Hydraulics**
Valve Enclosure Type: **Supplied With Hydraulics**
Low Oil Shut Down: **Yes, included in Hyd Pkg**
High Temp Oil Shut Down: **Yes, included in Hyd Pkg**
Low Oil Indicator: **Yes, included in Hyd Pkg**
Return Filter: **Provided with Hydraulics**
SS Tubing Upgrade: **TA,F&R lines,6'Frnt,9'Rr**
Quick Coupler Upgrade: **Stainless Steel Quick Couplers**
Front Plow Lift Q-Coup Upg: **(2PR) Frnt Plow Lift Q-Coupler**
Front Plow Rev Q-Coup Upg: **(2PR) Frnt Plow Rev Q-Coupler**
Wing Toe Q-Coup Upg: **(2PR) Wing Toe Q-Coupler (SW)**
Wing Heel Q-Coup Upg: **(2PR) Wing Heel Q-Coupler (SW)**
Spinner Q-Coup Upg: **(2PR) Spinner Q-Coupler (1S)**
Auger Q-Coupler Upg: **(2PR) Auger Q-Coupler**
Prewet Q-Coupler Upg: **Not Required**
Anti-Ice Coupler Upg: **Not Required**

Hydraulics Notes:





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 8
Quote #134907
Rev #106

Total configured price: \$113,040.00
Sourcewell package discount: 10% + freight
Discounted single package price: \$105,426.00
Package(s) : 1
Total: \$105,426.00

Signed: _____ Date: _____

Quote notes:

Reflective Tape on backside wing discharge of blade
Reflective Tape on top angle of wing moldboard
Hydraulics include controls to operate 3 lane anti icing unit





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 1
Quote #144203
Rev #28

To: CITY OF GENEVA, IL
Attn: JOE CZYSCZON
Quote Date: 1/15/2021
Valid Until: 2/14/2021
Sourcewell Contract# 080818-HPI
Sourcewell #: sourcewell
Quoted:

Quoted By: Rob Florio
Phone: 847-836-4996
Cell: 847-257-2452
Fax: 563-927-7108
Email: rflorio@hendersonproducts.com

Henderson Products is pleased to present the following quote. Please contact us if you have any questions.

Liquid anti-icing system

Tank Capacity / Hoop Kit: **1065 gallon tank, mild hoop kit, painted frame kit**
Boom: **Std 3 Lane Boom**
Nozzle Tips: **24 gal. per lane brass nozzle tips, standard**
Main Frame Material: **304SS stainless steel**
Hoop Kit: **Stainless Hoop Kit**
Wheel Guide Kit: **304SS stainless steel**
Leg Kit (supports empty unit only): **304SS stainless steel**
Ladder Kit: **304SS stainless steel**
Hose Reel Kit: **Yes**
Fluid Level Kit: **Yes**
Flowmeter: **Yes**
Trunnion Latch: **Stainless steel**
Tie down straps: **Yes**
Site guage: **Yes**

Installation Workup

Facility: **IDC-IL**
Chassis Delivery To Henderson: **Truck Dealer/Customer Delivers**
Completed Truck Delivery Method: **Henderson Delivers (100 miles or less)**

Prewet/Liquid System: **LAS Prewet System**
Controls: **Supplied by IDC (sales to order w/ hyd cntrls)**
Controls Installation: **Integrated w/ Hyd Controls**
Mount Type: **Slip-In Installation (ORDER TIEDOWN/TRUNNION AS NEEDED)**

Liquid Details:

Chassis Accessories: **Yes (SELECT RELATED OPTIONS BELOW)**
Pintle Plate: **Not Required for Job or Applic**
Pintle Hook: **Not Required**
Truck Wash: **Complete Truck Wash/Clean/Vac 1**
Warranty: **Standard 1 Year Warranty**
Reflective Tape: **Reflective Tape, Henderson Logo (60' Linear)**





HENDERSON

PRODUCTS, INC.

11921 SMITH DRIVE
HUNTLEY, IL 60142
PHONE: 847-836-4996
FAX: 563-927-7108

CUSTOMER QUOTE

Page 2
Quote #144203
Rev #28

Install Touch-up: **Basic Installation Touch-Up**

Electrical: **Yes (SELECT RELATED OPTIONS BELOW)**

Power Distribution Panel: **Power Distribution Panel**

Misc Electrical Supplies: **Req'd Misc Elect Supplies**

Worklight(s) QTY: **(QTY 1) Work Light (Select type below)**

Worklight (1) Type: **LED, Worklight, 4in Round (Optilux)**

Worklight (1) Gen Location: **On rear of body**

Backbone & Wire Standoffs: **10' Backbone (For SA)**

Electrical Spec Notes:

Total configured price: \$22,206.00

Sourcewell package discount: 10% + freight

Discounted single package price: \$19,338.00

Package(s) : 1

Total: \$19,338.00

Signed: _____

Date: _____

Quote notes:

1065 Gallon Slide in tank with 3 lane nozzle for Anti Icing

